Kent County Council

Salmestone Grange

Cost Plan Review Nr. 2

February 2020



DW Allen MRICS, FRSA, IMaPS PK Dadswell BSc, MRICS ME Dadswell BA (Hons), PgDip, MRICS SJ Parks BSc (Hons), MRICS, FQSi, ICIOB

Associate Director: OP Crisp BSc (Hons)

Consultant:

LM Brooks BSc (Hons), MRICS

3 Kings Row Armstrong Road Maidstone ME15 6AQ

T: 01622 676454

E: email@allendadswell.co.uk
W: www.allendadswell.com
















1.0 General Information

Description of Works

ADCC have been commissioned to review the 'Order of Cost Estimate for Arterial road and connections to existing road network' at Nash Road, Margate, produced by Sawyer & Fisher.

We have reproduced the Order of Cost Estimate in Section 2, and included our own estimate and commentary against each item for direct comparison. Our costs are extracted from our own Cost Estimate produced in Section 3. Note that in some instances costs are apportioned under different Series between Sawyer & Fisher's breakdown and our own and hence there are some disparities in the Series totals between Section 2 and Section 3.

We have also priced for the stopping up of Nash Road and the priority shift at Manston Road/Shottendane Road in Section 4. These works have not been priced in the original assessment by Sawyer and Fisher and hence there is no comparative cost.

Basis of Cost

Our costs are based at September 2019. We do not know when Sawyer and Fisher's Cost Estimate was produced and do not account for inflation in our direct comparison. Note that our amendments are indicated in red.

Drawings:

14-011-002 Rev C - Link Road - Phase 2 14-011-005 Rev C - Nash Road Closure

14-011-007 Rev C - Manston Road/Shottendane Road Priority Shift

C & A Consulting Engineers Technical Note, dated May 2017

Note that Sawyer & Fisher's costs are based on 14-011-002 Rev B, suggesting that their Cost Estimate was produced prior to the update to Revision C. The changes are minor and we feel any evaluation of the costs should be based on the latest revision. From the technical note the amendments are:

- Introduction of pedestrian facilities on each arm of the roundabout.
- Private drive access points to service road realigned to take the access away from the corners of the service road and made easier for manoeuvrability.
- Footway introduced along Nash Road where the priority junction is located.

Assumptions/Clarifications

Link Road - Phase 2

Sawyer and Fisher

- Removing existing trees allowance; £10k
- General allowance for other fencing; £10k
- Allowance for upgrade to existing drainage network to facilitate these works; £20k
- Allowance for lowering or diverting existing services; £50k
- Allowance for disposal of non-inert material; 25% of excavation volume
- Allowance for soft spots; £50k
- Allowance for re-enginaeering ground; £50k
- Allowance for phasing works to maintain use of Nash Road; £250k
- Allowance for traffic signage; £50k
- Allowance for road markings; £5k
- Assumed drainage and existing services are adjacent/close to the proposed works

We have commented on these assumptions in Section 2.



1.0 General Information

Allen Dadswell


- Allowed for an additional 215m of road where not shown on drawing at 7.3m wide, with 5m of footway and 4m of verge. No allowance has been made for junctions
- Allowed for additional cut at the new roundabout for reducing levels due to existing level difference between Manston Road and the adjacent field
- Allowed for extent of drainage, service diversions, and streetlighting
- Allowed for a 36 week construction period, including 12 weeks of traffic management
- Assumed construction build ups (based on existing Kent schemes)
- Allowed for excavation and filling of soft spots and other voids (10%), and disposal of unacceptable material (5%)
- Assumed 300mm of topsoil to be stripped and 150mm to be reinstated
- Allowed for all surplus material to be disposed off site
- Allowed for assorted signage and road markings
- Allowed for cold milling of surface course and overlaying with average 50mm thick regulating course and 30mm surface course for new road over existing carriageway. Assumed carriageway to remain where possible to maintain traffic flow during construction
- Assumed work to be undertaken under S278 and S38 agreements (allowed for a 50/50 split for the purposes of KCC fees)
- Assumed all works and preliminary costs independent of development costs

Shottendane Road/Manston Road Priority Shift & Nash Road Closure

- Allowed for a combined construction duration of 12 weeks, to be undertaken alongside Link Road Phase 2
- Priced preliminaries as an extra over main prelimaries for Link Road Phase 2
- Assumed all works to be undertaken under a single S278 agreement
- Allowed for extent of drainage, service diversions, and streetlighting
- Assumed construction build ups (based on existing Kent schemes)
- Allowed for excavation and filling of soft spots and other voids (10%), and disposal of unacceptable material (5%)
- Allowed for all surplus material to be disposed off site
- Allowed for assorted signage and road markings
- Nash Road Closure: Allowed for resurfacing of the surface course and an additional 50mm thick regulating course to full carriageway width where carriageway is being widened (Nash Road turning head). No resurfacing has been allowed for on the other arms of the junction
- Manston Road/Shottendane Road Priority Shift: Allowed for resurfacing of the surface course and an additional 50mm thick regulating course to full carriageway width along Manston Road (c. 65m) and to the Shottendane Road bellmouth

Exclusions

- Ecology/Archaeology
- LCA Part 1 costs
- Statutory Undertakers' costs (no information received)
- All works associated with the development / all other costs deemed included in the viability assessment. We note that the costs excluded from Sawyer & Fisher's cost plan and those above may require inclusion if they are not included elsewhere within the viability assessment.
- VAT





| | Sawyer & Fisher | | | | ADCC | S&F Revised | ADCC Revised | 1 |
|---|-----------------|--------|------|----------------------------|----------------------------|--------------|--------------|--|
| Description | Quantity | Unit F | Rate | Total | Total | | Total | Updated Comment |
| 200 Series - Site Clearance | | | | 64,000.00 | 46,973.00 | 55,973.00 | 51 972 00 | Breakout out hard material/cold milling included in S200 in ADCC Construction Breakdown. |
| 300 Series - Fencing | | | | 25,000.00 | 7,500.00 | | 15,000.00 | |
| 400 Series - Road Restraint Systems | | | | 30,000.00 | 0.00 | | 0.00 | |
| 500 Series - Drainage and Service Ducts | | | | 205,875.00 | 205,891.00 | 205,891.00 | | BWIC with utility diversions included under S2700 in ADCC Construction Breakdown. |
| 600 Series - Earthworks | | | | 481,550.00 | 253,545.50 | 425,654.00 | | Capping and completion of formation/sub-formation included under S700 in breakdown below, but are included under |
| 700 Series - Pavements | | | | 1,084,350.00 | 644,346.50 | 562,496.00 | | S600 in ADCC Construction Breakdown. |
| 1100 Series - Kerbs, Footways and Paved Areas | | | | 194,000.00 | 185,530.50 | - | 185,530.50 | |
| 1200 Series - Traffic Signs and Road Markings | | | | 60,000.00 | 41,400.00 | | 61,400.00 | |
| 1300 Series - Road Lighting Columns | | | | 220,000.00 | 48,200.00 | | | |
| 1400 Series - Electrical Work | | | | 147,000.00 | 31,700.00 | - | - | Connections included under S1300 in ADCC Construction Breakdown. |
| 1400 Series Electrical Work | | | | 147,000.00 | 31,700.00 | 147,000.00 | - | We have not received an updated breakdown for the landscaping but will accept S&F's costs due to increased |
| 3000 Series - Landscaping | | | | 88,600.00 | 22,071.00 | 37,905.00 | | landscaping costs being received. |
| Sood Series Editascaping | | | - | - | | | | |
| | | | | 2,600,375.00 | 1,487,157.50 | 1,815,450.00 | 1,624,235.50 | |
| Main Contractor's Preliminaries | | | 20% | 520,075.00 | 558,000.00 | 558,000.00 | | Note that we have priced as a weekly rate, not a percentage, which provides a more realistic allowance. We have assumed that there are no shared prelims with the wider development. |
| Traffc Management | | | 10% | 260,037.50 | 189,000.00 | 189,000.00 | 189,000.00 | We do not anticipate TM costs to be too onerous as the majority of the works are offline. |
| Design Fees | | | 5% | 130,018.75 | 0.00 | 90,772.50 | 0.00 | We would anticipate that the total design fees are no higher than 10% of the works costs. |
| Manston Road/Shottendane Road Priority Shift (NEW ITEM) | | | | | 132,998.50 | 132,998.50 | 132,998.50 | See breakdown in Section 4. |
| Nash Road Closure (NEW ITEM) | | | | | 204,813.00 | 204,813.00 | 204,813.00 | See breakdown in Section 4. |
| | | | - | 3,510,506.25 | 2,571,969.00 | 2,991,034.00 | 2,709,047.00 | |
| | | | | | | | | Deemed included in the ADCC rates, which are based on recent tender returns in the Kent area. We stand by our rates |
| Main Contractor's OH&P | | | 7% | 245,735.44 | 0.00 | 209,372.38 | 0.00 | which have been obtained from numerous tendered schemes, mainly in Kent. |
| Main Contractor's Risk Allowance | | | 5% | 175,525.31 | 128,598.45 | 149,551.70 | | 5% contingency allowance on construction works is acceptable. |
| Design Development | | | 5% | 175,525.31 | 0.00 | 149,551.70 | | Deemed included in the contingency. We understand what this is for and will agree on the basis that 5% client risk manner be adequate for a project of this nature. |
| | | | 3/0 | | | | | |
| Road Safety Audit Works Post Completion | | | - | 50,000.00 | 50,000.00 | | | Allowance is acceptable. |
| Client Risk Allowance | | | 5% | 4,157,292.31 207,864.62 | 2,750,567.45 137,528.37 | 177,475.49 | | Acceptable in combination with the 5% risk allowance above. |
| Client Design Fees | | | 10% | 415,729.23 | 275,056.75 | 354,950.98 | | 10% acceptable for overall design allowance |
| | | | 10% | | | | - | |
| Highways Authority Inspection Fees | | | | 150,000.00 | incl. below | 150,000.00 | incl. below | |
| S278 Supervision Fees (NEW ITEM) | | | | | 86,392.86 | | | KCC inspection fees at 10% of bond value for S38 works and the first 500k of S278 works, with a 3% fee on the remain |
| S38 Supervision Fees (NEW ITEM) | | | | | 137,528.37 | | | S278 bond value. For the purposes of assessment we have assumed that the S38 and S278 bond values are each 50% |
| S278 Fixed Fee for Transportaton Advice (NEW ITEM) | | | | | 17,719.00 | | 17,719.00 | the sub-total above. S278 works also incur a fixed fee of £17,719 for transportation advice to developer. |
| Commuted Sum for Maintenance Post Adoption | | | | 200,000.00 | 150,000.00 | 150,000.00 | 150,000.00 | Commuted sums are only incurred on non-standard assets and street lighting/landscaping/traffic signals. We do not |
| | | | | | | | | anticipate many non-standard assets for the works shown and have reduced the allowance accordingly. Also note the |
| | | | | | | | | we have not undertaken a detailed analysis of the commuted sums that may be incurred at this stage, and the figure |
| | | | | | | | | quoted is without prejudice to any commuted sum claims by KCC upon confirmation of the detailed design for the |
| | | | | | | | | works. |
| Total Order of Cost | | | L | 5,130,886.16 | 3,554,792.79 | 4,381,936.25 | 3,820,469.24 | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | 1 | | | | | | | |



| | Saw | yer & Fishe | r | ADCC | S&F Revised | ADCC Revised | 1 | |
|--|----------|-------------|----------|------------|-------------|--------------|-----------|--|
| Description | Quantity | | | Total | Total | | Total | Updated Comment |
| General Site Clearance | | | | | | | | |
| General site clearance | 10,000 | m² | 1.00 | 10,000.00 | 20,450.00 | 20,450.00 | 20,450.00 | ADCC allowance includes for breaking out retaining wall. |
| Breaking up existing kerbs | 300 | m | 20.00 | 6,000.00 | 6,600.00 | 6,600.00 | 6,600.00 | More kerbs will require breaking out, modifications to driveways are also shown along Manston Road. |
| Breaking up existing carriageway | 2,000 | m² | 15.00 | 30,000.00 | 13,923 | 13,923.00 | | See comments below under Existing Road. The rate is high, but it would be reasonable to include an allowance for cold milling. ADCC rate includes for cold milling and breaking out hard material. |
| Breaking up existing footpaths | 300 | m² | 10.00 | 3,000.00 | Incl. | 0.00 | Incl. | |
| Removal of existing trees, bushes & hedges | | | | | | | | |
| Removing hedges | | item | | 5,000.00 | 5,000.00 | 5,000.00 | 5,000.00 | Appropriate allowance. |
| Removing trees; allowance | | item | | 10,000.00 | 1,000.00 | 10,000.00 | 6,000.00 | Only appear to be two trees which will require removal. We will compromise on 6k. |
| | | | | 64,000.00 | 46,973.00 | 55,973.00 | 51,973.00 | |
| Fencing | | | | | | | | |
| Fencing to either side of junction of new road with Nash Road | 200 | m | 50.00 | 10,000.00 | 0.00 | 10,000.00 | 0.00 | Evidence of quantity? No evidence provided. |
| Fencing to railway side of new arterial prior to connection with existing road network | 100 | m | 50.00 | 5,000.00 | 0.00 | 5,000.00 | | What does this refer to? We would expect temporary fencing to be included under prelim or development costs. No evidence provided. |
| General allowance for other fencing | | item | | 10,000.00 | 7,500.00 | 10,000.00 | | The general allowance, taken with the fencing measurements above, seem high for the type of development and usage. We believe highway boundary fencing is unlikely. We will compromise on 15k overall. |
| | | | | 25,000.00 | 7,500.00 | 25,000.00 | 15,000.00 | |
| Road restraint system | | | | | | | | |
| Restraint barrier along re-aligned Nash Road to back of existing properties | 200 | m | 150.00 | 30,000.00 | 0.00 | 0.00 | 0.00 | What does this item refer to? We can't identify a need for VRS from the current plans. |
| | | | | 30,000.00 | 0.00 | 0.00 | 0.00 | |
| Highway drainage | | | | | | | | |
| Connection to existing strategic drainage system | | item | | 20,000.00 | 17,500.00 | 17,500.00 | 17,500.00 | ADCC allowances include for all works to existing drainage. |
| Main drain run | 535 | m | 125.00 | 66,875.00 | 84,391.00 | 84,391.00 | | Rate acceptable as average drainage rate. Quantity assumption is reasonable, depending on works required to existing drainage. ADCC allowance at 650m. |
| Branches to main drain run; single branch every 15m of main run | 40 | m | 450.00 | 18,000.00 | 12,600.00 | 12,600.00 | | Are these gully leads? Rate is very high per m, but is closer to our allowance if priced per gully. ADCC quantity allows of 3.5m/gully. |
| Gullies | 40 | nr | 150.00 | 6,000.00 | 15,400.00 | 15,400.00 | 15,400.00 | Rate very low (expect c. £370), are leads above? |
| Manholes | 15 | nr | 3,000.00 | 45,000.00 | 26,000.00 | 26,000.00 | 26,000.00 | Rate high. Assumed spacing is reasonable. |
| Existing services | | | | | | | | |
| Allowance for lowering/diverting existing services | | item | | 50,000.00 | 50,000.00 | 50,000.00 | | Allowance is reasonable in lieu of any information on extent of utilities which require diverting. However, the diversion of existing utility services can be costly and estimates should be requested from each affected utility company in order |
| | | | | 205,875.00 | 205,891.00 | 205,891.00 | | to provide an accurate figure. |



| | Sawyer & Fisher ADCC S&F Revised ADCC Revised | | | | | | | | | | | | |
|--|---|------|-------|------------|------------|------------|------------|---|--|--|--|--|--|
| Description | Quantity | | | Total | Total | | Total | Updated Comment | | | | | |
| | | | | | | | | | | | | | |
| Topsoil strip | | | | | | | | | | | | | |
| Strip topsoil; 150 thick; set aside for reuse in spoil heaps | 10,000 | m² | 1.00 | 10,000.00 | 13,603.50 | 10,000.00 | 12 602 50 | Effective rate/m³ is £6.70, which is higher than we expect. Need to understand the extents taken to comment on the | | | | | |
| Strip topson, 130 triick, set aside for reuse in spoir fleaps | 10,000 | ''' | 1.00 | 10,000.00 | 13,003.30 | 10,000.00 | | quantity. ADCC allowance for 300mm topsoil strip and no subsoil strip (topsoil expected to be thicker in greenfield). | | | | | |
| | | | | | | | | | | | | | |
| Strip subsoil; 300 thick; set aside for reuse in spoil heaps | 10,000 | m² | 2.00 | 20,000.00 | 0.00 | 20,000.00 | | Effective rate/m³ is £6.70. We will compromise at half the rate, and half the quantity given we have allowed for 300mm | | | | | |
| | | | | | | | | topsoil strip above. | | | | | |
| Earthworks | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| Assumed site does not require cut/fill and the road will be laid to approx | | | | | | | | There is a retaining wall running alongside Manston Road and a significant level difference between Manston Road and | | | | | |
| existing site levels | | | | | | | | the level of the retained soil. Assumption is acceptable for the majority of the road but expect some level changes to | | | | | |
| | | | | | | | | occur at the new roundabout. The additional cut is included in our breakdown. | | | | | |
| Excavate to reduce levels; assume 0.5m | 5,000 | m³ | 5.00 | 25,000.00 | 19,368.00 | 19,368.00 | 19,368.00 | Assumes 0.95m deep to be excavated across 10,000m². Carriageway area below at 7,100m² including on existing road | | | | | |
| | | | | • | • | | | (which may not be needed). This allowance would appear to be high given the assumption re. cut and fill, but may be | | | | | |
| | | | | | | | | okay given the comments above. | | | | | |
| Diameter off site | F 000 | 3 | 40.00 | 200 000 00 | 172 526 00 | 172 526 00 | 472 526 00 | This water is bight for dispassed off site. ADCC dispassed allowers a includes for subscilland to use! | | | | | |
| Dispose off site | 5,000 | m³ | 40.00 | 200,000.00 | 172,536.00 | 172,536.00 | 172,536.00 | This rate is high for disposal off site. ADCC disposal allowance includes for subsoil and topsoil. | | | | | |
| EO for disposing of non-inert material (assume 25%) | 1,250 | m³ | 75.00 | 93,750.00 | 14,528.00 | 93,750.00 | 62,500.00 | 25% is a very high allowance for non-inert material, and the rate is very high as an extra over. Note that breaking out | | | | | |
| | | | | | | | | carriageway and footway is included separately in S200. ADCC allowance includes for excavating unacceptable material | | | | | |
| | | | | | | | | at 5%, which accounts for non-inert, contaminated or hazardous material. We will compromise an extra over rate of | | | | | |
| | | | | | | | | £50/m³. | | | | | |
| Compaction | 10,000 | m² | 1.00 | 10,000.00 | 1,125.00 | 10,000.00 | 5,000.00 | We will compromise on 5k but believe this is excessive. | | | | | |
| | | | | | | | | | | | | | |
| Allowance for soft spots | | item | | 50,000.00 | 23,103.00 | 50,000.00 | | Say £50/m³ for excavating soft spots and replacing with capping material, suggests 1000m³ of spoft spots. This | | | | | |
| | | | | | | | | allowance is very high. We will compromise on 35k. | | | | | |
| Allowance for re-engineering ground to improveCBR (extent if required | | item | | 50,000.00 | 0.00 | 50,000.00 | 0.00 | Don't believe this will be required in addition to a capping layer. Suggest either/or - do we know what the CBR of the site | | | | | |
| not known) | | | | | | | | is? The S&F response doesn't address the question. Given the level of ground risk included and the depth of capping | | | | | |
| | | | | | | | | allowed for we do not believe it is appropriate to allow for further ground risk. We have been involved in a number of | | | | | |
| | | | | | | | | projects around Thanet and we have not experienced significantly bad CBR levels. | | | | | |
| Topsoiling | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| Topsoiling to verge; 150 thick | 5,700 | m² | 1.50 | 8,550.00 | 5,532.00 | 0.00 | 5,532.00 | What extent has been taken? S&F have now removed the item which we think is an error so our allowance remains | | | | | |
| Subsoil to verge; 300 thick | 5,700 | m² | 2.50 | 14,250.00 | 3,750.00 | 0.00 | 3 750 00 | Overall the allowances for earthworks are very high, however the reality may be that additional excavation is required | | | | | |
| Subson to verge, soo trick | 3,700 | ''' | 2.30 | 14,250.00 | 3,730.00 | 0.00 | - | as well as retaining structures due to the level differences. Suggest more information is required on the approach to the | | | | | |
| | | | | | | | | construction of the roundabout, or some clearly defined assumptions made. See ADCC cost breakdown for our | | | | | |
| | | | | | | | | estimation of the earthworks required. S&F have now removed the item which we think is an error so our allowance | | | | | |
| | | | | | | | | remains | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | 404 FF2 22 | 252 545 55 | 400 004 00 | 202 202 50 | | | | | | |
| | | | | 481,550.00 | 253,545.50 | 425,654.00 | 322,289.50 | 1 | | | | | |



| | | _ | yer & Fish | | ADCC | S&F Revised | | | | |
|---|----------|------|------------|--------------|------------|-------------|------------|---|--|--|
| Description | Quantity | Unit | Rate | Total | Total | | Total | Updated Comment | | |
| New Road | | | | | | | | | | |
| Sub-base & capping layer | | | | | | | | NB ADCC cost for 'Roundabout' included in 'New Road'. | | |
| Capping layer to carriageway pavement; assume 400mm thick | 1,520 | m³ | 40.00 | 60,800.00 | 59,708.00 | 60,800.00 | - | Is there any information on CBR available? What has been assumed? What is the extent of the new carriageway to Rate is acceptable. ADCC allowance for 250mm thick capping and compaction. | | |
| Type 1 sub-base to carriageway pavement; assume 150mm thick | 570 | m³ | 50.00 | 28,500.00 | 97,714.50 | 28,500.00 | 97,714.50 | Rate is acceptable. | | |
| Asphalt/Macacdam pavement | | | | | | | | | | |
| Base course to carriageway | 3,800 | m² | 50.00 | 190,000.00 | 244,260.00 | 190,000.00 | 244,260.00 | What thickness has been assumed? | | |
| Binder course to carriageway | 3,800 | m² | 15.00 | 57,000.00 | 86,848.00 | 57,000.00 | 86,848.00 | | | |
| Wearing course to carriageway | 3,800 | m² | 20.00 | 76,000.00 | 81,420.00 | 76,000.00 | 81,420.00 | Rate is high. | | |
| Speed humps | 7 | nr | 2,000.00 | 14,000.00 | 25,000.00 | 14,000.00 | 25,000.00 | Rate is acceptable. ADCC rate includes for the provision of a raised table to Manston Road service road. | | |
| Roundabout | | | | | | | | | | |
| Sub-base & capping layer | | | | | | | | | | |
| Capping layer to carriageway pavement; assume 400mm thick | 320 | m³ | 40.00 | 12,800.00 | Incl. | 12,800.00 | Incl. | We have included this above so no addition required. | | |
| Type 1 sub-base to carriageway pavement; assume 150mm thick | 120 | m³ | 50.00 | 6,000.00 | Incl. | 6,000.00 | Incl. | We have included this above so no addition required. | | |
| Asphalt/Macacdam pavement | | | | | | | | | | |
| Base course to carriageway | 800 | m² | 50.00 | 40,000.00 | Incl. | 40,000.00 | Incl. | We have included this above so no addition required. | | |
| Binder course to carriageway | 800 | m² | 15.00 | 12,000.00 | Incl. | 12,000.00 | Incl. | We have included this above so no addition required. | | |
| Wearing course to carriageway | 800 | m² | 20.00 | 16,000.00 | Incl. | 16,000.00 | Incl. | We have included this above so no addition required. | | |
| Existing road | | | | | | | | | | |
| Sub-base & capping layer | | | | | | | | | | |
| Capping layer to carriageway pavement; assume 400mm thick | 1,000 | m³ | 40.00 | 40,000.00 | 0.00 | 0.00 | | Would not expect the existing road to be broken out completely. Would expect the existing carriageway to be | | |
| Type 1 sub-base to carriageway pavement; assume 150mm thick | 375 | m³ | 50.00 | 18,750.00 | 0.00 | 0.00 | | resurfaced where possible and utilised as a running lane for existing traffic while works are ongoing. With that in would suggest these items are not required, although there may be areas in which full depth reconstruction is re- | | |
| Asphalt/Macacdam pavement | | | | | | | | | | |
| Base course to carriageway | 2,500 | m² | 50.00 | 125,000.00 | 0.00 | 0.00 | 0.00 | Confirm extent of these quantities. | | |
| Binder course to carriageway | 2,500 | m² | 15.00 | 37,500.00 | 28,616.00 | 28,616.00 | 28,616.00 | ADCC allowance is for regulating course & tack coat in lieu of binder. | | |
| Wearing course to carriageway | 2,500 | m² | 20.00 | 50,000.00 | 14,700.00 | 14,700.00 | 14,700.00 | | | |
| Tie-in to existing | | item | | 50,000.00 | 6,080.00 | 6,080.00 | 6,080.00 | Allowance is high, especially given comments above. | | |
| Allowance for phasing works | | item | | 250,000.00 | Incl. | 0.00 | Incl. | ADCC allowance incl. in prelims. Assumed minor phasing required as majority of carriageway can be built offline traffic controlled using temporary signals, with traffic diverted on to now road to complete kerb lines. | | |
| | | | | 1,084,350.00 | 644,346.50 | 562,496.00 | 644,346.50 | traffic controlled using temporary signals, with traffic diverted on to new road to complete kerb lines. | | |



| | | Saw | yer & Fishe | er I | ADCC | S&F Revised | ADCC Revised | |
|--|----------|------|-------------|-------------|------------|-------------|--------------|--|
| Description | Quantity | Unit | | Total | Total | | Total | Updated Comment |
| Kerbs | | | | | | | | |
| PCC HB2 kerbs to carriageways | 1,700 | m | 35.00 | 59,500.00 | 49,560.00 | 49,560.00 | 49,560.00 | Rate high. |
| PCC edgings to footways | 1,700 | m | 20.00 | 34,000.00 | 20,560.00 | 20,560.00 | 20,560.00 | Rate high. |
| Footways | | | | | | | | |
| Sub-base to footway; assume 150mm thick | 306 | m³ | 50.00 | 15,300.00 | Incl. | 0.00 | Incl. | |
| Footway surfacing; 100mm thick 2 course | 2,040 | m² | 30.00 | 61,200.00 | 112,950.50 | 112,951.00 | 112,950.50 | Total rate for footway is acceptable (£37.50/m²). |
| Tactile paving to crossing points including drop kerbs | 12 | nr | 2,000.00 | 24,000.00 | 2,460.00 | 2,460.00 | 2,460.00 | Rate is high. |
| | | ļ | | 194,000.00 | 185,530.50 | 185,531.00 | 185,530.50 | |
| Traffic signs | | | | | | | | |
| Allowance for traffic signage | | item | | 50,000.00 | 30,000.00 | 50,000.00 | 50,000.00 | Allowance is higher than we would expect. We will accept this but it is high. |
| Illuminated bollards | | item | | 5,000.00 | 6,400.00 | 5,000.00 | 6,400.00 | Allowance is reasonable. ADCC allowance includes for provision of (non-illuminated) square timber bollards. |
| Road markings | | | | | | | | |
| Allowance for road markings | | item | | 5,000.00 | 5,000.00 | 5,000.00 | 5,000.00 | Allowance is reasonable. |
| Traffic signals | | | | | | | | |
| Asuumed traffic signals or pedestrain crossings are not required | | | | Excl. | Excl. | Excl. | Excl. | Agreed, although an allowance will be required for the Nash Road Closure (deemed excluded from this cost plan) |
| | | 1 | | 60,000.00 | 41,400.00 | 60,000.00 | 61,400.00 | |
| Road Lighting columns (all provisional) | | | | | | | | |
| Road lighting columns; assumed qty | 40 | nr | 5,000.00 | 200,000.00 | 43,200.00 | 100,000.00 | | This rate is much higher than we have experienced anywhere in Kent - we would expect less than half of this rate all-in. What is assumption on quantity? Expect fewer street lights. We stand by our comment that £5,000 per column is excessive and we would query which lighting columns were required for the recently completed scheme referenced. We do not believe that such (presumably) high specification columns would be required in this area. |
| Feeder pillars; assumed qty at 1/5nr columns | 8 | nr | 2,500.00 | 20,000.00 | 5,000.00 | 10,000.00 | 5,000.00 | Would anticipate fewer feeder pillars. Our comment is unchanged. |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | • | 220,000.00 | 48,200.00 | 110,000.00 | 48,200.00 | |



| Sawyer & Fisher | | | | | | S&F Revised | ADCC Revised | 1 |
|--|----------|------|----------|------------|-----------|-------------|--------------|--|
| Description | Quantity | Unit | Rate | Total | Total | | Total | Updated Comment |
| Electrical work for road lighting & Traffic signs (all provisional) | | | | | | | | |
| | | | | | | | | |
| Trenching for street lighting inlcuding duct | 700 | m | 50.00 | 35,000.00 | 24,500.00 | 35,000.00 | | Rate is at the upper level of what we would expect. Our comment is unchanged. We note that S&F have halved the quantity of streetlights but have not halved the length of cabling & trenching or the quantity of lamps and feeder pillars. |
| | | | | | | | | quantity of streeting its suction of the recognition casting of the quantity of tamps and record plinars. |
| Cabling to street lighting in duct | 700 | m | 40.00 | 28,000.00 | Incl. | 28,000.00 | | Rate very high considering trenching included elsewhere (for the cabling alone we would expect closer to £6.50/m). Ou |
| | | | | | | | | comment is unchanged. |
| Cabling street lighting column and connection | 40 | nr | 1,000.00 | 40,000.00 | 7,200.00 | 40,000.00 | 7,200.00 | Rate is high considering the rates above. Our comment is unchanged. |
| Lamp to steet lighting column | 40 | nr | 500.00 | 20,000.00 | Incl. | 20,000.00 | Incl. | |
| | | | | | | | | |
| Connection to feeder pillar | 8 | nr | 500.00 | 4,000.00 | Incl. | 4,000.00 | Incl. | See comment above. |
| Allowance for electrical connection to new feeder pillar from existing | | item | | 20,000.00 | Incl. | 20,000.00 | 20,000.00 | We will accept this figure as an all in rate for connections and miscellaneous electrical works. |
| supply | | | | | | | | |
| | | | | 147,000.00 | 31,700.00 | 147,000.00 | 51,700.00 | |
| Diamting | | | | | | | | |
| Planting | | | | | | | | |
| Grass seeding to verges including raking | 5,800 | m² | 3.00 | 17,400.00 | 2,766.00 | | 2,766.00 | |
| Grass seeding to roundabout including raking | 400 | m² | 3.00 | 1,200.00 | Incl. | | Incl. | |
| | | | | | | | | |
| Tree planting to verge; allowance | 200 | nr | 350.00 | 70,000.00 | 19,305.00 | | | We would anticipate fewer trees - is this a planning requirement? ADCC allowance for tree planting and general planting. |
| | | | | | | | | pronting. |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | 99 600 00 | 22.074.00 | 0.00 | 22.074.00 | |
| | | | | 88,600.00 | 22,071.00 | 0.00 | 22,071.00 | 1 |





| Item | Description | Quantity | Unit | Rate | Total |
|------|--|--------------------|---------|------------|------------|
| | Series 100 - Preliminaries | | | | |
| А | General preliminaries | 36 | wks | 14,000.00 | 504,000.00 |
| В | Traffic Management | 36 | wks | 3,500.00 | 126,000.00 |
| С | TSCO | 36 | wks | 1,750.00 | 63,000.00 |
| D | Stats Co-ordinator | 8 | wks | 3,000.00 | 24,000.00 |
| E | E/O allowance for nightwork | 6 | wks | 5,000.00 | 30,000.00 |
| | _ | | | · | |
| | Ser l | ies 100 Carri I | ed to S | ummary £ | 747,000.00 |
| | Series 200 - Site Clearance | | | | |
| F | General site clearance, incl. signs and street furniture etc. | 12,300 | m² | 1.50 | 18,450.00 |
| G | Hedge clearance | 250 | m | 20.00 | 5,000.00 |
| н | Tree Clearance | 2 | nr | 500.00 | 1,000.00 |
| 1 | Breakout existing kerbs and remove to tip off site | 440 | m | 15.00 | 6,600.00 |
| J | Take up or down existing retaining wall and remove to tip off site | | item | | 2,000.00 |
| | Ser | ies 200 Carri | ed to S | ummary £ | 33,050.00 |
| | Series 300 - Fencing | | | | |
| К | Timber post and rail fencing | 300 | m | 25.00 | 7,500.00 |
| | Ser | ies 300 Carri | ed to S | ummary £ | 7,500.00 |
| | Series 500 - Drainage and Service Ducts | | | | |
| | Surface Water Carrier Drains | | | | |
| L | 225mm dia. drain including granular bed and surround exceeding 1m deep but not exceeding 1.5m deep | 130 | m | 100.00 | 13,000.00 |
| M | 225mm dia. drain including granular bed and surround exceeding 1.5m deep but not exceeding 2m deep | 195 | m | 121.00 | 23,595.00 |
| N | 300mm dia. drain including granular bed and surround exceeding 1.5m deep but not exceeding 2m deep | 228 | m | 140.00 | 31,920.00 |
| 0 | 300mm dia. drain including granular bed and surround exceeding 2m deep but not exceeding 2.5m deep | 98 | m | 162.00 | 15,876.00 |
| | | (| Carried | Forwards £ | 84,391.00 |



| Item | Description | Quantity | Unit | Rate | Total |
|------|--|---------------|---------|------------|------------|
| | | | rought | Forwards £ | 84,391.00 |
| | Series 500 - Drainage and Service Ducts Cont'd | | | | |
| | Surface Water Manholes | | | | |
| А | PCC manhole including cover and frame, 1200mm dia., depth to invert exceeding 1m but n/e 2m deep | 8 | nr | 1,500.00 | 12,000.00 |
| В | PCC manhole including cover and frame, 1200mm dia., depth to invert exceeding 2m but n/e 3m deep | 8 | nr | 1,750.00 | 14,000.00 |
| | Gullies and Gully Leads | | | | |
| С | PCC Gullies (450 x 750) | 40 | nr | 385.00 | 15,400.00 |
| D | Gully leads, 150mm dia. including concrete surround | 140 | m | 90.00 | 12,600.00 |
| E | Allowance for alterations to existing drainage | | item | | 15,000.00 |
| F | Allowance for raising and lowering ironwork | | item | | 2,500.00 |
| | Ser | ies 500 Carri | ed to S | ummary £ | 155,891.00 |
| | Series 600 - Excavation | | | | |
| | Excavation | | | | |
| G | Excavation of acceptable material class 5A, 300mm thick | 3,023 | m³ | 4.50 | 13,603.50 |
| Н | Excavation of acceptable material excluding class 5A | 4,304 | m³ | 4.50 | 19,368.00 |
| ı | Excavation of unacceptable material Class U1A/U1B | 227 | m³ | 12.00 | 2,724.00 |
| J | E/O for excavation in hard material | 189 | m³ | 27.00 | 5,103.00 |
| | Deposition of Fill | | | | |
| K | Deposition of acceptable material | 750 | m³ | 5.00 | 3,750.00 |
| | Disposal of Material | | | | |
| L | Disposal of acceptable material Class 5A to tip off-site | 2,608 | m³ | 28.00 | 73,024.00 |
| М | Disposal of acceptable material excl. Class 5A to tip off-site | 3,554 | m³ | 28.00 | 99,512.00 |
| N | Disposal of unacceptable material Class U1A/U1B | 227 | m³ | 52.00 | 11,804.00 |
| | Imported Material | | | | |
| 0 | Imported acceptable material Class 6F2 as fill for capping, 250mm thick | 1,357 | m³ | 40.00 | 54,280.00 |
| | | (| Carried | Forwards £ | 283,168.50 |

KENT COUNTY COUNCIL SALMESTONE GRANGE COST PLAN REVIEW NR. 2



| Item | Description | Quantity | Unit | Rate | Total |
|------|---|---------------|---------|------------|------------|
| | T | Bı | ought | Forwards £ | 283,168.50 |
| | Series 600 - Excavation Cont'd | | | | |
| | Soft Spots and Other Voids | | | | |
| А | Allowance for excavating soft spots and other voids | 453 | m³ | 17.00 | 7,701.00 |
| В | Allowance for filling soft spots and other voids | 453 | m³ | 34.00 | 15,402.00 |
| | Compaction of Fill | | | | |
| С | Compaction of acceptable material | 750 | m³ | 1.50 | 1,125.00 |
| D | Compaction of acceptable material 6F2 in capping | 1,357 | m³ | 2.00 | 2,714.00 |
| | Completion of Formation and Sub-Formation | | | | |
| E | Completion of formation | 5,429 | m² | 0.50 | 2,714.50 |
| F | Completion of sub-formation | 5,428 | m² | 0.50 | 2,714.00 |
| G | Perforate sub-base | 311 | m² | 4.00 | 1,244.00 |
| н | Topsoiling to verges and embankments, 150mm thick | 2,766 | m² | 2.00 | 5,532.00 |
| | Ser | ies 600 Carri | ed to S | ummary £ | 322,315.00 |
| | Series 700 - Pavements | | | | |
| | <u>Sub-Base</u> | | | | |
| ı | Type 1 sub-base, 350mm thick | 1,900 | m³ | 50.00 | 95,000.00 |
| J | Base course; HDM, 180mm thick | 5,428 | m² | 45.00 | 244,260.00 |
| К | Binder course; HDM, 60mm thick | 5,428 | m² | 16.00 | 86,848.00 |
| L | Surface course; Thin, 40mm thick | 6,408 | m² | 15.00 | 96,120.00 |
| М | Tie-in Detail | 160 | m | 38.00 | 6,080.00 |
| N | Cold milling, 50mm thick | 980 | m² | 9.00 | 8,820.00 |
| 0 | Regulating course, HDM, average depth 100mm thick | 98 | m³ | 282.00 | 27,636.00 |
| Р | Tack coat | 980 | m² | 1.00 | 980.00 |
| Q | Speed humps | 7 | nr | 2,500.00 | 17,500.00 |
| R | Allowance for raised table | | item | | 7,500.00 |
| | Ser | ies 700 Carri | ed to S | ummary £ | 590,744.00 |



| Item | Description | Quantity | Unit | Rate | Total |
|------|--|---------------|---------|----------|------------|
| | Series 1100 - Kerbs, Footways and Paved Areas | | | | |
| | <u>Footways</u> | | | | |
| А | Footway, consisting of; 150mm Type 1 sub-base, 60mm dense asphalt concrete binder, 25mm dense graded asphalt surface course | 2,935 | m² | 37.50 | 110,063.00 |
| В | Traffic Island, consisting of; 150mm Type 1 sub-base, 60mm dense asphalt concrete binder, 25mm dense graded asphalt surface course | 77 | m² | 37.50 | 2,887.50 |
| С | Tactile paving | 30 | m² | 82.00 | 2,460.00 |
| | Kerbs and Edgings | | | | |
| D | Precast concrete HB2 kerb, 125mm upstand | 1,770 | m | 28.00 | 49,560.00 |
| E | Precast concrete edging | 1,285 | m | 16.00 | 20,560.00 |
| | Serie Serie | es 1100 Carri | ed to S | ummary £ | 185,530.50 |
| | Series 1200 - Traffic Signs and Road Markings | | | | |
| F | Allow for assorted signage | | item | | 30,000.00 |
| G | Road markings | | item | | 5,000.00 |
| Н | Illuminated bollards | 6 | nr | 600.00 | 3,600.00 |
| 1 | Square timber bollards | 8 | nr | 350.00 | 2,800.00 |
| | Serie | es 1200 Carri | ed to S | ummary £ | 41,400.00 |
| | Series 1300 - Road Lighting Columns | | | | |
| J | 8m high lighting column & cabling with LED lantern | 24 | nr | 1,800.00 | 43,200.00 |
| К | Allowance for connections and other electrical works | 24 | nr | 300.00 | 7,200.00 |
| L | Feeder pillars | 2 | nr | 2,500.00 | 5,000.00 |
| | Serie | s 1300 Carri | ed to S | ummary £ | 55,400.00 |
| | Series 1400 - Electrical Work for Road Lighting and Traffic Signs | | | | |
| М | Allowance for trench and duct for street lights/illuminated traffic signs | 700 | m | 35.00 | 24,500.00 |
| | | | | | |
| | | | | _ | |
| | Serie | es 1400 Carri | ea to S | ummary £ | 24,500.00 |

KENT COUNTY COUNCIL SALMESTONE GRANGE COST PLAN REVIEW NR. 2



| Item | Description | Quantity | Unit | Rate | Total |
|------|---|---------------|---------|-----------|-----------|
| | Series 2700 - Works for Statutory Undertakers | | | | |
| A | Utility Diversions/Supplies | | item | | 50,000.00 |
| | | es 2700 Carri | | ummary f | 50,000.00 |
| | Serie | :5 2700 Carri | eu 10 3 | uninary E | 30,000.00 |
| | Series 3000 - Landscape & Ecology | | | | |
| В | Allow for seeding to verges and embankments | 2,766 | m² | 1.00 | 2,766.00 |
| С | Allow for general planting | 2,341 | m² | 5.00 | 11,705.00 |
| D | Tree Planting | 20 | nr | 380.00 | 7,600.00 |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | Serie | s 3000 Carri | ed to S | ummary £ | 22,071.00 |



KENT COUNTY COUNCIL SALMESTONE GRANGE COST PLAN REVIEW



4.1 Priority Shift / Nash Road Closure Summary

| Elemental Summary | Priority Shift | Nash Road Closure |
|---|----------------|----------------------|
| CEDITO 100 D. H | 44,000,00 | 50,000,00 |
| SERIES 100 - Preliminaries | 44,000.00 | 58,000.00 |
| SERIES 200 - Site Clearance | 12,875.00 | 9,500.00 |
| SERIES 500 - Drainage and Service Ducts | 6,800.00 | 21,700.00 |
| SERIES 600 - Earthworks | 3,492.00 | 6,285.00 |
| SERIES 700 - Pavements | 38,710.00 | 21,515.00 |
| SERIES 1100 - Kerbs, Footways and Paved Areas | 11,321.50 | 14,203.00 |
| SERIES 1200 - Traffic Signs and Road Markings | 10,800.00 | 63,500.00 |
| SERIES 2700 - Works for Statutory Undertakers | 5,000.00 | 10,000.00 |
| SERIES 3000 - Landscape & Ecology | 0.00 | 110.00 |
| | | |
| Sub Total £ | 132,998.50 | 204,813.00 |



4.2 Priority Shift / Nash Road Closure Breakdown

| | | Priority Shift | | | | Nash Road Closu | | | 2 |
|------|--|----------------|-----------------------------|------------|-----------|-----------------|----------|------------|-----------|
| Item | Description | Quantity | Unit | Rate | Total | Quantity | Unit | Rate | Total |
| | Series 100 - Preliminaries | | | | | | | | |
| А | E/O General preliminaries | 4 | wks | 2,500.00 | 10,000.00 | 8 | wks | 2,500.00 | 20,000.00 |
| В | Traffic Management | 4 | wks | 3,500.00 | 14,000.00 | 8 | wks | 3,500.00 | 28,000.00 |
| С | E/O allowance for nightwork | 2 | wks | 5,000.00 | 10,000.00 | 2 | wks | 5,000.00 | 10,000.00 |
| D | Accommodation Works to the school | | item | | 10,000.00 | | item | | 0.00 |
| | <u>Ser</u> | ies 100 Carri | ed to S | ummary £ | 44,000.00 | | <u> </u> | | 58,000.00 |
| | Series 200 - Site Clearance | | | | | | | | |
| E | General site clearance, incl. signs and street furniture etc. | 1,100 | m² | 10.00 | 11,000.00 | 700 | m² | 10.00 | 7,000.00 |
| F | Breakout existing kerbs and remove to tip off site | 125 | m | 15.00 | 1,875.00 | 150 | m | 15.00 | 2,250.00 |
| G | Take up or down existing Pedestrian Guardrail and remove to tip off-site | 0 | m | 25.00 | 0.00 | 10 | m | 25.00 | 250.00 |
| | Ser | ies 200 Carri | es 200 Carried to Summary £ | | 12,875.00 |) | | | 9,500.00 |
| | Series 500 - Drainage and Service Ducts | | | | | | | | |
| | Gullies and Gully Leads | | | | | | | | |
| Н | PCC Gullies (450 x 750) | 4 | nr | 385.00 | 1,540.00 | 6 | nr | 385.00 | 2,310.00 |
| 1 | Gully leads, 150mm dia. including concrete surround | 14 | m | 90.00 | 1,260.00 | 21 | m | 90.00 | 1,890.00 |
| J | Allowance for alterations to existing drainage | | item | | 2,500.00 | | item | | 15,000.00 |
| К | Allowance for raising and lowering ironwork | | item | | 1,500.00 | | item | | 2,500.00 |
| | Ser | ies 500 Carri | ed to S | ummary £ | 6,800.00 | | | | 21,700.00 |
| | Series 600 - Excavation | | | | | | | | |
| | <u>Excavation</u> | | | | | | | | |
| L | Excavation of acceptable material class 5A, 300mm thick | 0 | m³ | 4.50 | 0.00 | 4 | m³ | 4.50 | 18.00 |
| М | Excavation of acceptable material excluding class 5A | 62 | m³ | 4.50 | 279.00 | 112 | m³ | 4.50 | 504.00 |
| N | Excavation of unacceptable material Class U1A/U1B | 3 | m³ | 12.00 | 36.00 | 6 | m³ | 12.00 | 72.00 |
| 0 | E/O for excavation in hard material | 26 | m³ | 27.00 | 702.00 | 38 | m³ | 27.00 | 1,026.00 |
| | Deposition of Fill | | | | | | | | |
| Р | Deposition of acceptable material | 13 | m³ | 5.00 | 65.00 | 20 | m³ | 5.00 | 100.00 |
| | Disposal of Material | | | | | | | | |
| Q | Disposal of acceptable material Class 5A to tip off-site | 0 | m³ | 28.00 | 0.00 | 1 | m³ | 28.00 | 28.00 |
| R | Disposal of acceptable material excl. Class 5A to tip off-site | 49 | m³ | 28.00 | 1,372.00 | 92 | m³ | 28.00 | 2,576.00 |
| S | Disposal of unacceptable material Class U1A/U1B | 3 | m³ | 52.00 | 156.00 | 6 | m³ | 52.00 | 312.00 |
| | Imported Material | | | | | | | | |
| Т | Imported acceptable material Class 6F2 as fill for capping, 250mm thick | 11 | m³ | 40.00 | 440.00 | 21 | m³ | 40.00 | 840.00 |
| | Soft Spots and Other Voids | | | | | | | | |
| U | Allowance for excavating soft spots and other voids | 7 | m³ | 17.00 | 119.00 | 12 | m³ | 17.00 | 204.00 |
| | Allowance for filling soft spots and other voids | 7 | m³ | 34.00 | | 12 | m³ | 34.00 | 408.00 |
| | - · | | | Forwards £ | 3,407.00 | | | Forwards £ | 6,088.00 |



4.2 Priority Shift / Nash Road Closure Breakdown

| | | Priority Shift | | | | Nash Road Closure | | | | |
|------|--|--|----------|----------|-------------------|--|----------------|--------|-------------------|--|
| Item | Description | Quantity Unit Rate Brought Forwards £ | | | Total 3,407.00 | Quantity Unit Rate Brought Forwards £ | | | Total 6,088.00 | |
| | Series 600 - Excavation Cont'd | | | | , | | | | , | |
| | Compaction of Fill | | | | | | | | | |
| A | Compaction of acceptable material | 13 | m³ | 1.50 | 19.50 | 20 | m³ | 1.50 | 30.00 | |
| | Compaction of acceptable material 6F2 in capping | 11 | m³ | 2.00 | | 21 | m³ | 2.00 | 42.00 | |
| | Completion of Formation and Sub-Formation | | ''' | 2.00 | 22.00 | 21 | "" | 2.00 | 42.00 | |
| С | Completion of formation | 43 | m² | 0.50 | 21.50 | 86 | m ² | 0.50 | 43.00 | |
| | Completion of sub-formation | 44 | m² | 0.50 | | 84 | m ² | 0.50 | 42.00 | |
| | Topsoiling to verges and embankments, 150mm thick | 0 | m² | 2.00 | 0.00 | 20 | m ² | 2.00 | 40.00 | |
| _ | | | | | | 20 | <u> </u> ''' | 2.00 | | |
| | | ies 600 Carri | led to S | ummary £ | 3,492.00 | | | | 6,285.00 | |
| | Series 700 - Pavements | | | | | | | | | |
| | <u>Sub-Base</u> | 4.5 | 3 | 50.00 | 750.00 | 20 | 3 | 50.00 | 4 500 00 | |
| F | Type 1 sub-base, 350mm thick | 15 | m³ | 50.00 | 750.00 | 30 | m³ | 50.00 | 1,500.00 | |
| | Base course; HDM, 180mm thick | 42 | m² | 45.00 | 1,890.00 | | m² | 45.00 | 3,825.00 | |
| | Binder course; HDM, 60mm thick | 42 | m² | 16.00 | 672.00 | 85 | m² | 16.00 | 1,360.00 | |
| | Surface course; Thin, 40mm thick | 762 | m² | 15.00 | 11,430.00 | 350 | m² | 15.00 | 5,250.00 | |
| J | Tie-in Detail | 72 | m | 38.00 | 2,736.00 | 58 | m | 38.00 | 2,204.00 | |
| | High Friction Surfacing | | | | | | | | | |
| К | High friction surfacing | 80 | m² | 22.00 | 1,760.00 | 0 | m² | 22.00 | 0.00 | |
| | Cold Milling | | | | | | | | | |
| L | Cold milling, 70mm thick | 200 | m² | 10.60 | 2,120.00 | 100 | m² | 10.60 | 1,060.00 | |
| М | Cold milling, 50mm thick | 720 | m² | 9.00 | 6,480.00 | 265 | m² | 9.00 | 2,385.00 | |
| N | Regulating course, HDM, average depth 50mm thick | 36 | m³ | 282.00 | 10,152.00 | 13 | m³ | 282.00 | 3,666.00 | |
| 0 | Tack coat | 720 | m² | 1.00 | 720.00 | 265 | m² | 1.00 | 265.00 | |
| | Ser | ies 700 Carri | ied to S | ummary £ | 38,710.00 | 0 | | | 21,515.00 | |
| | Series 1100 - Kerbs, Footways and Paved Areas | | | | | | | | | |
| | <u>Footways</u> | | | | | | | | | |
| P | Footway, consisting of; 150mm Type 1 sub-base, 60mm dense asphalt concrete binder, 25mm dense graded asphalt surface course | 69 | m² | 37.50 | 2,588.00 | 106 | m² | 37.50 | 3,975.00 | |
| | Traffic Island, consisting of; 230mm Type 1 sub-base, 60mm dense asphalt concrete binder, 25mm dense graded asphalt surface course | 5 | m² | 37.50 | 187.50 | 0 | m² | 37.50 | 0.00 | |
| R | Footway resurfacing, consisting of; 50mm dense asphalt concrete binder, 20mm dense graded asphalt surface course | 200 | m² | 24.00 | 4,800.00 | 100 | m² | 24.00 | 2,400.00 | |
| S | Tactile paving | 3 | m² | 82.00 | 246.00 | 34 | m² | 82.00 | 2,788.00 | |
| | Kerbs and Edgings | | | | | | | | | |
| Т | Precast concrete HB2 kerb, 125mm upstand | 125 | m | 28.00 | 3,500.00 | 180 | m | 28.00 | 5,040.00 | |
| | | | | | | | | | | |
| | Serie | es 1100 Carri | ied to S | ummary £ | 11,321.50 | | | | 14,203.00 | |



4.2 Priority Shift / Nash Road Closure Breakdown

| | | Priority Shift | | | Nash Road | | | Road Closure | | | |
|------|---|----------------|---------|----------|-----------|----------|------|--------------|-----------|--|--|
| Item | Description | Quantity | Unit | Rate | Total | Quantity | Unit | Rate | Total | | |
| | Series 1200 - Traffic Signs and Road Markings | | | | | | | | | | |
| А | Allow for assorted signage | | item | | 5,000.00 | | item | | 10,000.00 | | |
| В | Road markings | | item | | 2,500.00 | | item | | 2,500.00 | | |
| С | Burn off road markings | | item | | 1,000.00 | | item | | 1,000.00 | | |
| D | Traffic signals (Proposed crossing point) | | item | | 0.00 | | item | | 30,000.00 | | |
| E | Allowance for alterations of traffic signals | | item | | 0.00 | | item | | 20,000.00 | | |
| F | Illuminated bollards | 2 | nr | 600.00 | 1,200.00 | 0 | nr | 600.00 | 0.00 | | |
| G | Refuge beacons | 1 | nr | 1,100.00 | 1,100.00 | 0 | nr | 1,100.00 | 0.00 | | |
| | Serie | es 1200 Carri | ed to S | ummary £ | 10,800.00 | | | | 63,500.00 | | |
| | Series 2700 - Works for Statutory Undertakers | | | | | | | | | | |
| н | Utility Diversions | | item | | 5,000.00 | | item | | 10,000.00 | | |
| | Serio | es 2700 Carri | ed to S | ummary £ | 5,000.00 | | | | 10,000.00 | | |
| | Series 3000 - Landscape & Ecology | | | | | | | | | | |
| ı | Allow for seeding to verges and embankments | 0 | m² | 0.50 | 0.00 | 20 | m² | 0.50 | 10.00 | | |
| J | Allow for general planting | 0 | m² | 5.00 | 0.00 | 20 | m² | 5.00 | 100.00 | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | Serie | es 3000 Carri | ed to S | ummary £ | 0.00 | | | | 110.00 | | |